



At what point is the tendon tested with air? It seems it needs to be before the 'concrete' is placed correct?

The air test should be performed after the strands are stressed and prior to grouting. This is required by the PTI M55.1 Section 5.5.4. Testing prior to concrete placement is not typically required. However, in some special cases may be helpful and/or required.