



Does the Contractor need to demonstrate they can kick in the backup grout plant up and pumping without exceeding 30 minutes?

The location and timing of using the backup grout plant should be included in the plan as one of the troubleshooting items. Typically, this is not demonstrated or mocked up, but practicing this would not be a bad idea, especially if access is a challenge.